Construction of Extension Canal of Purok-4 Estancia DD Brgy. Estancia, Malinao, Albay NAME OF PROJECT:

LOCATION:

AMOUNT:

Php2,000,000.00 BILL OF QUANTITIES AND COST PROPOSAL SUBJECT:

ITEM NO.	DESCRIPTION		UNIT	QUANTITY	UNIT COST (PhP)	AMOUNT (Php)
1.0	Construction of Camp,Temporary Facilities & Movement of Equipment		L.S.	1.0		
	0	stancetion Cofety, and Hoolth		1.0		
2.0	Construction Safety and Health		L.S.	1.0		
3.0	Cana	al Works (m) 615				
0.0		Common Excavation	cu.m.	136.68		
		Structural Backfill/backfilling	cu.m.	68.34		
		Concrete Class "B" With Forms	cu.m.	65.94		
		Concrete Class "B" Without Forms	cu.m.	54.67		
		Reinforcing Steel Bars	kgs	5,064.90		
		AggregateSub Base Course	cu.m.	54.67		
		1 00 0		-1	Sub-Total	
4.0	End	Check 1 Unit				
		Common Excavation	cu.m.	0.50		
		Structural Backfill/backfilling	cu.m.	0.25		
	4.3	Concrete Class "B" With Forms	cu.m.	0.50		
	4.4	Reinforcing Steel Bars	kgs	6.00		
	4.5	Wooden Flush Board (Yakal)	bd.ft	1.00		
	4.5	AggregateSub Base Course	cu.m.	0.10		
				-	Sub-Total	
5.0	Divis	sion Box 2 Units				
	5.1	Common Excavation	cu.m.	1.00		
		Structural Backfill/backfilling	cu.m.	0.50		
	5.3	Concrete Class "B" With Forms	cu.m.	0.72		
	5.4	Concrete Class "B" Without Forms	kgs	0.28		
		Reinforcing Steel Bars	cu.m.	20.00		
	5.6	Wooden Flush Board (Yakal)	bd.ft	6.00		
	5.7	AggregateSub Base Course	cu.m.	0.30		
	Sub-Total					
6.0	Tractor Crossing 3 Units					
		Common Excavation	cu.m.	0.90		
		Structural Backfill/backfilling	cu.m.	0.45		
		Concrete Class "B" With Forms	cu.m.	0.75		
		Reinforcing Steel Bars	kgs	34.63		
	6.5	AggregateSub Base Course	cu.m.	0.30		
	Sub-Total					
	1					
7.0	Billb	oard/ Marker	LOT	1.00		
	Sub-Total Sub-Total					
	Total Co					
	Administrative Cost 3.00%					
	Total Project Cost					
~						

Note: All Taxes, contractors profit and hauling costs are included in unit cost per item

Name and Signature of Bidder	