

NAME OF PROJECT: **Construction of Extension Canal of Cabangon DD**
 LOCATION: Brgy. Cabangon, Bacacay, Albay
 AMOUNT: **Php3,000,000.00**
 SUBJECT: BILL OF QUANTITIES AND COST PROPOSAL

ITEM NO.	DESCRIPTION	UNIT	QUANTITY	UNIT COST (PhP)	AMOUNT (Php)
1.0	Construction of Camp, Temporary Facilities & Movement of Equipment	L.S.	1.0		
2.0	Construction Safety and Health	L.S.	1.0		
3.0	Canal Works (m) 1015				
	2.1 Common Excavation	cu.m.	203.00		
	2.2 Structural Backfill/backfilling	cu.m.	101.50		
	2.3 Concrete Class "B" With Forms	cu.m.	105.74		
	2.4 Concrete Class "B" Without Forms	cu.m.	81.20		
	2.5 Reinforcing Steel Bars	kgs	7,657.00		
	2.6 AggregateSub Base Course	cu.m.	81.20		
				Sub-Total	
4.0	End Check 1 Units				
	4.1 Common Excavation	cu.m.	0.50		
	4.2 Structural Backfill/backfilling	cu.m.	0.25		
	4.3 Concrete Class "B" With Forms	cu.m.	0.50		
	4.4 Reinforcing Steel Bars	kgs	6.00		
	4.5 Wooden Flush Board (Yakal)	bd.ft	1.00		
	4.5 AggregateSub Base Course	cu.m.	0.10		
				Sub-Total	
5.0	Division Box 2 Units				
	5.1 Common Excavation	cu.m.	1.00		
	5.2 Structural Backfill/backfilling	cu.m.	0.50		
	5.3 Concrete Class "B" With Forms	cu.m.	0.72		
	5.4 Concrete Class "B" Without Forms	kgs	0.28		
	5.5 Reinforcing Steel Bars	cu.m.	20.00		
	5.6 Wooden Flush Board (Yakal)	bd.ft	6.00		
	5.7 AggregateSub Base Course	cu.m.	0.30		
				Sub-Total	
6.0	Tractor Crossing 3 Units				
	6.1 Common Excavation	cu.m.	0.90		
	6.2 Structural Backfill/backfilling	cu.m.	0.45		
	6.3 Concrete Class "B" With Forms	cu.m.	0.85		
	6.4 Reinforcing Steel Bars	kgs	36.00		
	6.5 AggregateSub Base Course	cu.m.	0.30		
				Sub-Total	
7.0	Billboard/ Marker	LOT	1.00		
				Sub-Total	
				Total Project Cost	
					~

Note: All Taxes, contractors profit and hauling costs are included in unit cost per item

 Name and Signature of Bidder