



**Department of Agriculture  
Regional Field Office No. 5  
San Agustin, Pili, Camarines Sur**

**BILL OF QUANTITIES AND COST PROPOSAL**

NAME OF PROJECT:  REPAIR AND IMPROVEMENT OF NURSERY SHED 2		Appropriation (Php) Source of Funds Issued Obligated Authority Mode of Implementation Released Calendar Days to Complete		P 180,000.00 HVCDP 2023  By Contract  60 CD  Upon Received of NTP			
Location: CNLRRS, CALAGASAN, DAET, CAMARINES NORTE		Starting Date					
PROJECT CATEGORY:  PRODUCTION FACILITY							
PROJECT DESCRIPTION/SCOPE OF WORK: a) Replacement of damaged net with 70% Shade PP Woven Net b) Clearing, cleaning and grubbing of shed vicinity c) Use of 2" dia GI Pipe S40 for the replacement of corroded pipes							
MINIMUM EQUIPMENT REQUIREMENT				TECHNICAL PERSONNEL REQUIRED			
Description	No.	Description	No.	Description	No.	Description	No.
Minor Tools	Enough					Skilled Laborer	3
Welding Machine	1					Unskilled Laborer	5
Angle Grinder	1					Foreman	1
ITEM	DESCRIPTION		UNIT	QUANTITY	UNIT COST (Php)	TOTAL AMOUNT	
B.9	MOBILIZATION/DEMOBILIZATION		lot	1.00			
801	REMOVAL OF WORKS		lot	1.00			
902	STEEL WORKS		kg	91.80			
903	SCAFFOLDINGS		lot	1.00			
1003	ROOFING WORKS AND SIDE COVER		sqm	54.00			
<b>TOTAL PROJECT COST</b>							

Note: All taxes, contractor's profit and hauling cost are included in unit cost per item.

\_\_\_\_\_  
NAME AND SIGNATURE OF BIDDER