



**Department of Agriculture**  
**Regional Field Office No. 5**  
 San Agustin, Pili, Camarines Sur

**BILL OF QUANTITIES AND COST PROPOSAL**

NAME OF PROJECT:  REPAIR AND IMPROVEMENT OF SCREENHOUSE		Appropriation (Php) Source of Funds Issued Obligated Authority Mode of Implementation Released Calendar Days to Complete		<p>₱ 150,000.00 HVCDP 2023</p> <p>By Contract</p> <p>60 CD</p> <p>Starting Date</p> <p>Upon Received of NTP</p>			
Location: ARDC, BUANG TABACO CITY, ALBAY							
PROJECT CATEGORY: PRODUCTION FACILITY							
PROJECT DESCRIPTION/SCOPE OF WORK: a) Replacement of damaged net with 70% Shade PP Woven Net. b) Installation of steel matting (galvanized welded wire) for encloement of the perimeter c) Installation of Sprinkler System d) Gate Framing: Use 1" dia GI Pipe S40							
MINIMUM EQUIPMENT REQUIREMENT				TECHNICAL PERSONNEL REQUIRED			
Description	No.	Description	No.	Description	No.	Description	No.
Minor Tools	Enough					Skilled Laborer	3
Welding Machine	1					Unskilled Laborer	5
						Foreman	1
ITEM	DESCRIPTION		UNIT	QUANTITY	UNIT COST (Php)	TOTAL AMOUNT	
B.9	MOBILIZATION/DEMOBILIZATION		lot	1.00			
801	REMOVAL OF WORKS		lot	1.00			
902	STEEL WORKS		kg	86.61			
903	SCAFFOLDINGS		lot	1.00			
1003	ROOFING WORKS		sqm	72.00			
1008, 1010	GATE AND SPRINKLER IRRIGATION		lot	1.00			
<b>TOTAL PROJECT COST</b>							

Note: All taxes, contractor's profit and hauling cost are included in unit cost per item.

\_\_\_\_\_  
 NAME AND SIGNATURE OF BIDDER